FTI-CDK1: Vehicle Coverage and Preparation Notes

| | RSTECH, LLC. SUPPORT - 1(888) 820-3690, EXT. 203 |
|---|---|
| " | SUPPORT - 1(888) 820-3690, EXT. 203 |

| Make | Model | Year | Install | CAN | Lights | всм | POC | I/O Changes |
|--------|----------|---------|---------|--------|-------------|-----|-----|------------------|
| DL-CH5 | | | | | Park / Auto | | | Green White/Blue |
| Dodge | Ram 1500 | 2007-08 | Type 3 | SKREEM | A-MUX | | | |
| | | | | | | | | |

Firmware:

Covered vehicles utilize the BLADE-AL(DL)-CH5 firmware, flash module and update the controller firmware before installing.

Warning:

SKREEM damage may result from excess pressure placed upon the SKREEM connector and harness during disassembly. Fully exposing the SKREEM so that the connector release can be fully depressed will help avoid damaging the module.

This install does not use the included START and MUX connections, please ensure that the unused connections are properly insulated and secured for safety.

Lights:

Type A (MUX) parking light connections are located at the 10-pin headlight switch, an additional relay and 1K Ohm resistor are required to complete the circuit interface.

Type B (+) parking light connections are not required for this installation type. Please ensure that the unused wires are properly insulated and secured for safety.

RAP:


Type D (-) retained accessory power (RAP) handling requires connecting controller rearm output to the driver's door pin wire, *purple* in the driver kick panel harness.

FTI-CDK1 - Installation and Configuration Notes

- A Connections not required.
- B Connections not required.
- MUX parking lights require an additional relay and 1K Ohm resistor.
- P RAP shutdown connection, configure POC for RAP (option #31).

| AMMININA MARINA MARIANTA MARINA MARIN | |
|--|--|
| A THE TENTH OF THE PERSON OF T | |
| THE PART OF THE PA | |
| WALLEY WA | |
| The second of th | |
| | |

| | FEATURE COVERAGE | | | | | | | | | | | | | | | | | | |
|------------------|------------------|-----------|-------------|---------------|------------------|--|--|--|--|-------------|--|--------------|--------------|----------------|-------------|-------------------|----------------|--|--|
| 0 | 0 | 0 | 0 | 0 | 0 | | | | | 0 | | 0 | 0 | 0 | 0 | 0 | 0 | | |
| IMMOBILIZER DATA | PRIORITY UNLOCK | DOOR LOCK | DOOR UNLOCK | ARM OEM ALARM | DISARM OEM ALARM | | | | | DOOR STATUS | | RAP SHUTDOWN | BRAKE STATUS | E-BRAKE STATUS | тасн оптрит | DATA/MUX IGNITION | PARKING LIGHTS | | |



5x - VIN invalid, contact support

6x - VIN mismatch, confirm firmware and vehicle entry




ALL IN ONE CHRYSLER/DODGE/JEEP

Patent No. US 8,856,780 CA 2759622

BLADE-AL(DL)-CH5-EN

Doc. No.: ##52028## 20180717

CARTRIDGE INSTALLATION



Slide cartridge into unit. Notice button under LED.

2

Ready for Module Programming Procedure.

MODULE PROGRAMMING PROCEDURE

