
FTI-FDK2: Vehicle Coverage and Preparation Notes									
Make	Model	Year	Install	CAN	Lights	OEM RS	POC	I/O Changes	
DL-FM8 Ford	Escape STD Key AT	2020-21	Туре 7	GTWY	Park / Auto HAZ	N/A	N/A	Green White/Blue N/A	
Firmware:     This installation requires BLADE-AL(DL)-FM8 firmware, flash module and update the controller firmware before beginning the installation. This firmware requires the use of tach monitoring, please ensure that tach is programmed to avoid malfunction.       Harness headlight connector not compatible, configure POC for hazard lights [30] (momentary) or [23] (latched), connect to BCM connector C2280D (white 72-pin connector), pin #12 (brown/yellow).       Confirm vehicle compatibility on the module flashing site before proceeding with installation.       See compatibility note below.									
Compatibility requirements: In order to confirm firmware compatibility, please confirm vehicle is equipped with active hood pin switch. Hood ajar warning must be displayed in instrument cluster when hood is open and ignition is on. Additional dealer programming and switch installation or hood ajar circuit manipulation* is required if hood ajar warning is not displayed when confirming.									
FTI-FDK	2: Installation and Co	onfiguratio	n Notes						
A BLUE	A BLUE MS CAN WIRES FOR PART 1 PROGRAMMING						BOTH Red & Red/Wh connected with high	n current application.	
B BRO	WN HS CAN WIRES FOR PAF	T 2 PROGRA	MMING				Parking Light		
C SECURE UNUSED BLADE CONNECTOR TO MAIN HARNESS							Starter 🗖	Image: Starter   Imag	
		FEATU	JRE COVEF	RAGE			M7000/7200	Cut loop for A/T Cut loop for A/T Cut loop for A/T Cut loop for A/T Cut loop for A/T	
ANN	MMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM	DISARM OEM ALARM	z	BRAKE STATUS O HOOD STATUS O TACH OUTPUT O HEATED MIRRORS O	HEATED SEATS	CTRL	START CONTRACTION		



#### LED Programming Error Codes Module LED flashing RED during programming

1x - No CAN activity, confirm BLADE 1 or BLADE 2 connector
 2x - No ignition, confirm BLADE 1 or BLADE 2 connector
 3x - No communication with BCM, confirm compatibility
 4x - Unable to activate OEM RS, confirm compatibility
 5x - Unable to activate OEM RS, firmware will not work

Fast Blink - CAN connection, reverse BLADE 1/2 connector

# INSTALL GUIDE

B	LRC	DE
	SERIES	


### DOORLOCK INTERFACE FORD/LINCOLN

Patent No. US 8,856,780 CA 2759622 COM-BLADE-AL(DL)-FM8-EN

Doc. No.: ##74735## 20210310

Page 18 of 20


CARTRIDGE INSTALLATION



Slide cartridge into unit. Notice button under LED.

2

Ready for Module Programming Procedure.



# INSTALL GUIDE

В	L			2		כ	E	
	S	E	R		E	S		

## DOORLOCK INTERFACE FORD/LINCOLN

Patent No. US 8,856,780 CA 2759622

#### Page 20 of 20

COM-BLADE-AL(DL)-FM8-EN

#### Doc. No.: ##74735## 20210310

## TAKE OVER PROCEDURE - TO THE VEHICLE OWNER

### NOTE

I All vehicle doors must be closed and locked prior to remote start sequence.



Press unlock on OEM or aftermarket remote or request switch.

DO NOT PRESS BRAKE PEDAL. Set ignition to ON position. Wait 2 seconds for key validation.

